

CfQ Reference SL 01/26

Quotation to:

Birdlife Malta

57/28, Abate Rigord Street,

Ta' Xbiex XBX1120

VAT: MT1252-2003

Applicant Details – 1A

Name and surname of representative	
ID number	
Company Name	
VAT number	
Postal Address	
Email Address	
Contact Number	
Date	
Signature	

Financial Bid – 1B

Item Number	Item Description	Quantity	Unit Price excl VAT	VAT rate	Total Price incl VAT
1	The removal of the existing dislodged blocks forming part of the sea wall, as well as the removal of displaced stone paving blocks adjacent to the wall.	30 32			
2	The extraction of all dislodged dowels.	30			
3	Retrieval of limestone blocks that have been displaced/washed away into the sea/saltpan in shallow water	25			

4	The reinstatement of the underlying sub-base beneath the paving.	Per 1m ²			
5	The placement beneath the paving of appropriate fill or concrete suitable for marine applications together with a geotextile layer.	13m ³ 2.5m x 35m			
6	The stone paving will then need to be relayed and the joints regouted.	10.5m ²			
7	The retrieved limestone blocks shall be assessed for reuse and reinstated where deemed suitable. Provide replacement limestone blocks (tal-qawwi) to replace blocks that are not reusable, measuring approximately 40 cm x 50cm by 100cm long	Each			
8	The canal area and its supporting base shall be cleared and reconstructed, including the reinstatement of 2 lintels spanning over the canal opening.	1m x 1m x 1m			
9	Where the existing lintels are found to be unsuitable following retrieval, new lintels shall be supplied and installed. These lintel blocks (tal-qawwi) measure 166cm x 40cm x 40cm.	2 lintels			
10	The sea wall shall be fully reinstated, including the correct placement and dowelling of limestone blocks with 20mm stainless steel dowels 1 m long, one per block, to restore the structural integrity and function of the coastal sea wall.	35m ²			
Any Discount		Specify Rate			
Total in EURO (€)					

Signature:_____

Name and Surname:_____